



CORRIGENDUM No.1

Contract title: “Dredging of Jegricka river within ECOWAM project”

Publication ref.: HUSRB/1602/11/0010-TD-02

The following alterations and/or corrections are made:

(1) In Volume 3. Technical specifications (EARTH WORKS TECHNOLOGY, Section 29+588 km to 37+892 km, 2. Earth works)

The former text:

2. Earth works

2.1. Sludge removal by using a long reach excavator in line with designed characteristic profiles and volume statement table. The removed material shall be disposed near the riparian zone. Calculation shall be performed per m³ of removed material.....143,800.00 m³.

2.2. Removal of the material from the streambed and disposal of material in the riparian zone by using a bulldozer. Logging and inspection path made of the removed material by using a bulldozer. Due to various canal widths, 80% of the removed material shall be transported to the riparian zone by using a long reach excavator. Calculation shall be performed per m³ of the removed material115,040.00 m³.

Shall read as new text:

2. Earth works

2.1. Sludge removal by using a long reach excavator in line with designed characteristic profiles and volume statement table. The removed material shall be disposed near the riparian zone. Calculation shall be performed per m³ of removed material.....143,800.00 m³.

2.2. Removal of the material from the streambed and disposal of material in the riparian zone by using a long reach excavator. Logging and inspection path made of the removed material by using a long reach excavator. Due to various canal widths, 80% of the removed material shall be transported to the riparian zone by using a long reach excavator. Calculation shall be performed per m³ of the removed material115,040.00 m³.

All other terms and conditions of the Volume 3. Technical specifications remain unchanged.